



Jacksonville
District

2005 Tri-Service Infrastructure Conference
St. Louis, Missouri 1-4 August 2005

Presentation for

**Development of Design Criteria
for the Rio Puerto Nuevo
Contract 2D/2E Channel Walls**

Janna Tanner, Jacksonville District
David Shiver, Jacksonville District
Daniel Russell, INCA Engineers

INCA
ENGINEERS INC.



Jacksonville
District

The Rio Puerto Nuevo

Contract 2D/2E Channel Walls

- ❑ Why is the Flood Control Project needed?
- ❑ What wall systems are used?
- ❑ How were the wall systems selected?
- ❑ What design criteria was used?
- ❑ How were the walls designed?

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Project Description

- ❑ Includes 11.2 miles of channel improvements, using 8 different channel sections, through the middle of San Juan.
- ❑ Includes 30 bridge modifications and replacements, 2 debris basins, and 2 stilling basins.


2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Project Location



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Rio Puerto Nuevo Project

Jacksonville
District




2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Rio Puerto Nuevo Site Plan

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Contract 2D/2E Description

- ❑ Convert an existing trapezoidal earthen ditch, the Rio Puerto Nuevo, into a 150 foot wide by 15 foot deep rectangular channel.
- ❑ Channel walls and bottom designed separately.


2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Typical Channel Cross Section

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Wall Design Goals

- ❑ Develop least cost wall system for 10,700 lineal feet of channel wall with an average exposed face of 23 feet.
- ❑ Satisfy hydraulic design, real estate, and construction constraints.

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Hydraulic Design Constraints

- Channel geometry must remain rectangular (i.e. vertical walls) for hydraulic and R/W acquisition reasons.
- Wall facing system must have a Manning's roughness constant consistent with finished concrete (i.e. 0.013)



Jacksonville
District

Wall System Selection

- ❑ **VE** selected 5 wall systems & 2 proprietary wall systems.
- ❑ **Further study** selected 2 wall types that were fully designed and detailed in the construction documents.
 - ❑ **Master Pile Wall.** The master pile wall consists of a series structural pipe piles alternating with lagging pipe piles.
 - ❑ **Drilled Shaft Wall.** The drilled shaft wall consists of initially installed lean concrete lagging piles with structural drilled shafts installed between and overlapping the lagging piles.

2005 Tri-Service
Infrastructure
Conference


INCA
ENGINEERS INC.




Jacksonville
District

Original & Revised Master Pile Wall

(Plan View)



Original




Revised



Jacksonville
District

Drilled Shaft Wall (Plan View)





Jacksonville
District

Geotechnical Site Issues

- Interlayered Silt and Clay overlies Weathered Bedrock. The top of weathered rock varies in elevation from -30 to -80.
- 3 different geographical profiles were idealized and used to analyze the different reaches of the channel.


2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Typical Geologic Profile



2005 Tri-Service
Infrastructure
Conference





Jacksonville
District

Geologic Profile Types for Pile Design

Geologic Profile Type	Top of Weathered Bedrock Elevation (feet)	Channel Reach Station Interval (Structural Design Reach)	Total Length of Channel Reaches (feet)
A	-30	117+50 to 121+50 (A1) 132+50 to 139+00 (A2)	1050
B	-50	88+30 to 89+50 (B1) 95+50 to 117+50 (B2) 121+50 to 132+50 (B3)	3420
C	-80	89+50 to 95+50 (C1) 139+00 to 147+40 (C2)	1440

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Soil & Rock Properties

Soil Layer	Stress State	Internal Friction Angle (degrees)	Cohesion (psf)	Total Unit Weight (pcf)	Saturated Unit Weight (pcf)
Interlayered Silt & Clay (CH)	Q	$\phi = 0$	$c = 720$	110	115
	S	$\phi' = 25$	$c' = 0$	110	115
	R	$\phi = 15$	$c = 400$	110	115
Weathered Bedrock	Q	$\phi = 0$	$c = 3,000$	125	125
	S	$\phi' = 35$	$c' = 0$	125	125
	R	$\phi = 15$	$c = 750$	125	125

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Subgrade Reaction Moduli Used for LPile Analysis

Elevation (feet)	Geologic Profile Type		
	A	B	C
	Subgrade Reaction Modulus, K_h (pci)		
-15	16	16	16
-20	22	22	22
-25	30	30	30
-30	200	43	43
-35	200	61	61
-40	200	76	76
-45	200	93	93
-50	200	200	103
-55	200	200	111
-60	200	200	120
-65	200	200	128
-70	200	200	138
-75	200	200	148
-80	200	200	200
-85	200	200	200

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Design Philosophy

Working Stress vs. Ultimate Strength Design

- ❑ The Master Piles were designed using working stress design.
- ❑ The Drilled Shafts were designed using the ultimate strength, load factor design.

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Serviceability Design

- ❑ Design for serviceability addresses the concerns related to displacements of the loaded structure, both global stability and deflection.

- ❑ For a diaphragm wall there are three stability concerns
 - ❑ Global rotation (deep-seated failure)
 - ❑ Rotational failure (due to inadequate penetration)
 - ❑ Flexural failure (structural inadequacy)

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Rotational Failure

Rotational failure is due to inadequate penetration and is prevented by long pile action

- ❑ Good practice to ensure long pile action
 - ❑ Have 2 zero-deflection points
 - ❑ Have nearly zero deflection at the pile tip.

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Deflection Criteria

- ❑ **Good practice is to limit the wall deflection.**
Deflection criteria for the static load case has been developed (by team consensus not by EM) to limit the ratio of the top of wall deflection vs. the mudline deflection to 2% of the exposed wall face height.

- ❑ **Seismic deflection does not have a limit, but this structure:**
 - ❑ **Must remain elastic during an OBE event**
 - ❑ **May be plastic during an MDE event, but no collapse is permitted**


2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Pile Deflected Shape



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Design Procedure

- ❑ Determine the **structural demand** on the walls
- ❑ Calculate the **depth of embedment necessary to produce long pile action**
- ❑ Calculate the **factor of safety for wall stability**
- ❑ Calculate the **structural capacity of the walls**

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Structural Demand

- **Calculate individual loads** using classical soil mechanics and then combine results into load cases. The individual loads are:
 - Hydrostatic (channel side)
 - Porewater (landside)
 - Construction surcharge
 - Active condition soil
 - Wall inertia
 - Dynamic soil
 - Hydrodynamic porewater

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Pile Embedment

- ❑ Determine embedment by using LPILE
- ❑ Iterate to shorten pile in order to
 - ❑ Have barely 2 zero deflection points, and
 - ❑ Near zero tip rotation w/one zero deflection point near the tip

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Stability Check

- Use EM 1110-2-2504 “Design of Sheet Pile Walls” for 3 failure modes
 - Deep seated failure
 - Rotational failure
 - Structural failure

- EM 1110-2-2504 is used since it’s for deep foundations

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District


Results

- ❑ Deep seated failure – Geotechnical analysis used Slope/W by Ensoft and determined that the walls, as designed, are stable
- ❑ Rotational failure – Wall as designed has long pile action so is stable for rotational failure
- ❑ Structural failure – Wall is designed to have adequate strength



Jacksonville
District

Wall Geometry



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Load Cases

- The load cases are as follows
 - Load Case 1 Construction
 - Load Case 2A – Flood (Undrained)
 - Load Case 2B – Flood (Drained)
 - Load Case 3A – Drawdown (Undrained)
 - Load Case 3B – Drawdown (Drained)
 - Load Case 4A – OBE Seismic (Undrained)
 - Load Case 4B – MDE Seismic (Undrained)


2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Load Case 1 Construction




LOAD CASE 1: CONSTRUCTION




Jacksonville
District

Load Case 2A & 2B – Flood (Undrained & Drained)



LOAD CASE 2A: FLOOD (UNDRAINED SOILS)




LOAD CASE 2B: FLOOD (DRAINED SOILS)




Jacksonville
District

Load Case 3A & 3B – Drawdown (Undrained & Drained)



LOAD CASE 3A: DRAWDOWN (UNDRAINED SOILS)




LOAD CASE 3B: DRAWDOWN (DRAINED SOILS)




Jacksonville
District

Load Case 4A & 4B – OBE Seismic & MDE Seismic (Undrained)



LOAD CASE 4A: OBE SEISMIC (UNDRAINED SOILS)



LOAD CASE 4B: MDE SEISMIC (UNDRAINED SOILS)



Jacksonville
District

Design Results

- Shear Forces and Bending Moments
 - Drilled Shaft Wall

Design Reach B1	Vu	Static	241 k
		Dynamic	94 k
	Mu	Static	3791 k-ft
		Dynamic	1643 k-ft

Design Reach C2	Vu	Static	242 k
		Dynamic	115 k
	Mu	Static	4166 k-ft
		Dynamic	2089 k-ft



Jacksonville
District

Design Results

- Shear Forces and Bending Moments
 - Master Pile Wall

Design Reach B1	V	Static	182 k
		Dynamic	81 k
	M	Static	2797 k-ft
		Dynamic	1348 k-ft

Design Reach C2	V	Static	151 k
		Dynamic	101 k
	M	Static	2280 k-ft
		Dynamic	1728 k-ft

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Design Results

- ❑ The static load cases govern the wall design for all design reaches.
- ❑ The static shears and moments are approximately twice the dynamic shears and moments.
- ❑ Since the static cases govern, the seismic coefficient method is an acceptable procedure.

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Design Results

- Maximum Displacements
 - Drilled Shaft Wall

Design Reach	Location	Load Type	Displacement
B1	Top	Static	3.70 in
		Dynamic	2.34 in
	Mudline	Static	1.49 in
		Dynamic	0.78 in
C2	Top	Static	3.80 in
		Dynamic	3.21 in
	Mudline	Static	1.40 in
		Dynamic	1.00 in



Jacksonville
District

Design Results

- Maximum Displacements
 - Master Pile Wall

Design Reach	Location	Load Type	Displacement
B1	Top	Static	6.02 in
		Dynamic	2.84 in
	Mudline	Static	2.42 in
		Dynamic	0.90 in
C2	Top	Static	5.54 in
		Dynamic	3.99 in
	Mudline	Static	1.95 in
		Dynamic	1.19 in

- Again, the static load cases govern the wall design for all design reaches.



Jacksonville
District

Displacement Serviceability


Design	Relative Displacement (%)	
	Drilled Shaft	Master Pile
A1	0.7	1.1
A2	0.7	1.1
B1	0.8	1.4
B2	0.8	1.3
B3	0.9	1.3
C1	0.8	1.4
C2	0.8	1.2

- All displacements meet the established deflection criteria.




Jacksonville
District


Master Pile Wall



TYPICAL WALL SECTION
MASTER PILE WALL



PLAN
MASTER PILE WALL




KNUCKLE DETAIL
MASTER PILE WALL




Jacksonville
District


Drilled Shaft Wall



TYPICAL WALL SECTION
DRILLED SHAFT WALL




PLAN
DRILLED SHAFT WALL



SEE SECTION B/- FOR ADDITIONAL
DETAILS

SECTION A



SECTION B

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Conclusion

- ❑ Set idealized soil/rock parameters that can be used for long reaches of the project
- ❑ Set serviceability criteria for deflections
- ❑ Analyze and design to resist
 - ❑ Deep seated failure
 - ❑ Rotational failure
 - ❑ Structural failure
- ❑ Let the market determine the least cost solution – Foreign Steel price fluctuating

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Master Pile Wall for Contract 2A

- ❑ 800 ft of wall installed
- ❑ 48" dia, 3/4" wall, ASTM A252, Gr 3 ($f_y = 45$ ksi) pipe piles, with average pile length of 70 ft
- ❑ intermediate pair of AZ 18, ASTM A572, Gr 50, steel sheet piles, with an average length of 35 ft

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shaft Wall at Bechara Industrial Area

- ❑ 2000 linear feet of culvert
- ❑ Top down excavation
- ❑ Secant pile wall

2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Drilled Shaft Walls at Bechara Industrial Area

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Drilled Shaft Walls at Bechara Industrial Area

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Drilled Shaft Walls at Bechara Industrial Area

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Drilled Shaft Walls at Bechara Industrial Area

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Drilled Shaft Walls at Bechara Industrial Area

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shafts at De Diego Expressway Bridge



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shafts at De Diego Expressway Bridge



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shaft Walls at I-90 Mercer Island, Washington



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shaft Walls at I-90 Mercer Island, Washington



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shaft Walls at I-90 Mercer Island, Washington



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Drilled Shaft Walls at I-90 Mercer Island, Washington



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



SR 526 Interchange / I-5 Northbound Ramp

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



SR 526 Interchange / I-5 Northbound Ramp

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



SR 526 Interchange / I-5 Northbound Ramp

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



SR 526 Interchange / I-5 Northbound Ramp

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



SR 526 Interchange / I-5 Northbound Ramp

Jacksonville
District



2005 Tri-Service
Infrastructure
Conference

INCA
ENGINEERS INC.



Jacksonville
District

Thank You

INCA
ENGINEERS INC.