

U.S. Army
Corps of
Engineers



GEI
Consultants

Ben Foreman

912 652-5370, Office

912 677-6085, Cell

US Army Corps of Engineers,
Savannah District

ben.c.foreman@sas02.usace.army.mil

U.S. Army
Corps of
Engineers



SEISMIC REMEDIATION OF THE CLEMSON UPPER AND LOWER DIVERSION DAMS; DEEP SOIL MIX CONSTRUCTION

Lee Wooten, P.E.
GEI Consultants, Inc.
Winchester, MA

Ben Foreman
U.S. Army Corps of Engineers
Savannah District



Bids

Clemson Total Bid Summary		Production Soil Cement Bid Summary	
Government Estimate	\$7,768,587	Winning Bid	\$107/yard³
Winning & Low Bid	\$7,744,657	Low Bid	\$70/yard³
High Bid	\$12,592,400	High Bid	\$199/yard³
Average	\$9,248,526	Average	\$126/yard³

Winning Bid: **RAITO Inc.** of Crofton, Maryland

Bids

U.S. Army
Corps of
Engineers



GEI
Consultants



Additional Soil Cement Bid Summary

Winning & Low Bid

\$220/yard³

High Bid

\$819/yard³

Average

\$556/yard³

Construction – Soil Mix Equipment

- Large track mounted rig
- Six in-line, 3-foot-diameter, ~50-foot-long soil mix augers
- Four electrical motors drive the augers at either 20 or 40 rpms




Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



- Auger mixing blades over the bottom 10 ft of the shafts
- Overlap adjacent mixing columns by 1 ft
- Average wall width of 2.76 feet
- Adjacent augers vertically offset by 1 ft



Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



GEI
Consultants



Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



GEI
Consultants



Batch and Pumping Plant



Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



GEI
Consultants



Tanker truck off-loading cement

Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



Pumping Rate Monitors and Controls



Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



Pump

Flow Meters



Construction – Soil Mix Equipment

U.S. Army
Corps of
Engineers



GEI
Consultants



Batch Plant Monitor and Controls



Construction – QA/QC

U.S. Army
Corps of
Engineers



Monitored Parameters:

- Depth
 - Time
 - Flow Rate
- 
- Injected Cement / Foot
- Cable Load
 - Electrical Motor Load
 - Verticality
- 
- Resistance



Typical Installation Record

Installation Records

PAGE 1

Project Name: Clemson

Element # : UDSW40196

Rig # : 1

7 / 28 / 2004

Mixing System Design Data	Depth (ft)	Slurry Injection Volume (gal/ft)		Speed (ft/min)	
		Down	Up	Down	Up
1st Layer	8.5	1.0	0.0	40.0	40.0
2nd Layer	50.0	17.6	0.0	3.5	5.5
3rd Layer	-----	-----	-----	-----	-----
4th Layer	-----	-----	-----	-----	-----

Depth (ft)	Time (mm:ss)	Speed (ft/min)	Rotation (rpm)	Slurry Injection Volume (gal)						Energy Index
				Column1	Column2	Column3	Column4	Column5	Column6	
0.0	0:00									
3.0	0:25	7.2	19	9.8	7.1	7.2	8.4	7.4	7.5	39
6.0	1:58	1.5	19	21.3	22.7	20.7	21.8	22.3	22.6	222
8.5	3:50	0.6	17	78.0	73.1	73.5	74.3	71.1	74.3	805
9.0	0:24	1.2	19	17.6	18.3	18.3	18.1	18.5	18.3	377
12.0	1:27	2.0	19	54.6	54.4	54.3	54.4	54.5	54.3	198
15.0	1:27	2.0	19	52.0	52.3	52.2	52.1	52.2	52.3	194
18.0	1:13	2.4	19	58.6	58.3	57.3	58.4	58.0	58.1	144
21.0	1:08	2.6	19	64.6	64.4	63.2	64.5	64.5	64.4	76
24.0	0:56	3.2	38	53.5	53.4	55.2	53.3	53.4	53.4	40
27.0	1:37	1.8	40	57.1	58.6	58.7	58.6	58.1	57.3	110
30.0	1:04	2.8	40	59.6	54.3	56.0	53.7	56.6	57.4	35
33.0	1:05	2.7	40	56.5	56.6	57.3	54.9	57.1	56.9	36
36.0	3:00	1.0	39	56.9	59.8	61.0	60.6	60.6	62.3	275
39.0	1:30	2.0	21	81.3	75.5	81.2	79.5	81.2	82.0	84
42.0	0:57	3.1	19	53.7	53.8	53.9	53.8	53.9	53.8	96
45.0	2:14	1.3	19	62.7	63.5	63.6	63.1	64.1	63.8	348
47.0	3:58	0.5	19	111.4	110.4	112.3	40.6	39.6	40.2	1069 ***
47.1	1:31	0.0	19	33.9	34.2	34.2	32.4	32.8	30.9	1337
48.0	0:31	0.0	19	0.5	0.5	0.5	0.5	0.5	0.5	**

Construction- QA/QC

U.S. Army
Corps of
Engineers



Construction – Planned QA/QC

U.S. Army
Corps of
Engineers



QA/QC – Wet Grab Soil-Cement Samples

Frequency:

- Two sets of samples per wall
- Not less than one set per work shift per rig

Set: Consists of 4 samples each at top, middle, bottom depths

Procedure:

- Screen samples on 1-inch sieve
- Cut particles retained to just pass the 1-inch sieve and then to be remixed with sample
- Collect enough soil-cement per sample to make four full cylinders (6-inch diameter by 12-inch height)

Unconfined tests: @ 7 days, 28 days(2), and 56 days; (12 @ 28)

Construction – Planned QA/QC

U.S. Army
Corps of
Engineers



QA/QC - Core Samples

Where:

- Two locations per test section (Test section was a single wall)
- Two locations within any production wall where wet grab samples do not meet strength criteria

When: Only after strength from unconfined tests on wet grab cylinders indicate that soil-cement strength is unsuitable

Type of core: Continuous, double tube or triple tube, minimum 3-inch diameter

Supplemental coring: If recovery less than 85 % in any run

Testing: Unconfined compression on six samples per boring

Construction – QA/QC

U.S. Army
Corps of
Engineers



Test Sections

Two test sections per dam.

Establish **base procedures** for installation of production walls.

If $f'_{sc} < \text{criteria}$, then:

- use **smaller S**, wall spacing, that will meet criterion or
- Contractor may **modify procedures** (e.g. higher cement ratio) during production to increase f'_{sc} .

Construction – Planned QA/QC

U.S. Army
Corps of
Engineers



QA/QC – Soil-Cement Strength Criteria

Average 28-day compressive strength for each wall:

- **Average f'_{sc} (28 day) ≥ 77.4 psi x (S / Wa)**

Average of all samples (12) from six wet grab locations or all samples (12) from two core borings (when wet grab samples fail)

- **One sample per wall may have $f'_{sc} < 2/3$ criterion**

Construction – QA/QC

U.S. Army
Corps of
Engineers



Wet Grab Samplers




Construction- Excavation of Berm

U.S. Army
Corps of
Engineers



GEI
Consultants



Design vs Actual – Schematic Section

Construction- Excavation of Berm

U.S. Army
Corps of
Engineers



GEI
Consultants



Lower Dam



Construction- QA/QC

U.S. Army
Corps of
Engineers



Sampler plugged with soil from unimproved zone

Construction- QA/QC

U.S. Army
Corps of
Engineers



GEI
Consultants



Large sampler mounted on drill shaft



Construction – QA/QC

Attempts at Wet-
Grab Sampling
(Unsuccessful)



Construction – QA/QC

Coring Rig for Soil-Cement Sampling



Construction- QA/QC

U.S. Army
Corps of
Engineers



GEI
Consultants



Construction- QA/QC

U.S. Army
Corps of
Engineers



GEI
Consultants



Core in core box; note plastic sheath and burlap

Construction- QA/QC

U.S. Army
Corps of
Engineers



GEI
Consultants



Logging of core and selecting test specimens

Construction – Actual QA/QC

U.S. Army
Corps of
Engineers



QA/QC – Soil-Cement Strength Criteria

Average 28-day compressive strength for each wall:

- **Average f'_{sc} (28 day) ≥ 77.4 psi x (S / Wa)**

Average of all samples (12) from six wet grab locations or all samples (12) from two core borings (when wet grab samples fail)


- **One sample per wall may have $f'_{sc} < 2/3$ criterion**
- ***Criteria evolved to single core boring for a day's production; minimum six samples per core; one sample may have $f'_{sc} < 2/3$ average; additional core borings as required***

Construction- Excavation of Berm

U.S. Army
Corps of
Engineers



GEI
Consultants



Design vs Actual – Schematic Section

Construction- Drain Construction

U.S. Army
Corps of
Engineers



GEI
Consultants



Trench box and dewatering pump station

Construction- Drain Construction

U.S. Army
Corps of
Engineers



Installation of discharge line; note slot in longitudinal wall

Construction- Drain Construction

U.S. Army
Corps of
Engineers



Cleanouts on drain line



Construction – Soil-Cement Production Mixes

U.S. Army
Corps of
Engineers



Cement Injection Rates:

- **840 lb/yd³ (500 kg/m³)** at start
- **670 lb/yd³ (400 kg/m³)** at end

Water-Cement Ratio: **0.6 to 0.7**

Construction – Penetration “Refusal” Criteria

U.S. Army
Corps of
Engineers



- Advancement Rate < 0.2 foot/minute
- Cable load $<$ one ton
- Duration $>$ one minute

Construction- Problems and Remedies

U.S. Army
Corps of
Engineers



Problems:

- Zones where f'_{sc} of soil cement did not meet criteria, probably due to organic content and/or low pH, in ~13% of walls
- Difficult to judge and achieve **penetration** into dense strata, in ~20% of walls

Remedy:

- **Additional elements** or walls

Construction – Lessons

U.S. Army
Corps of
Engineers



- **Expect zones of significant deviation** of f'_{sc} (allow some random deviations, correct deviation trends or patterns)
- **Cover as large a range of soils** as possible in design mix testing
- Test soil samples for **pH** and **organic content**
- Use **coring** and not wet grab sampling for QA
- Use **recovery** and core **RQD** or continuity as part of the QA criteria

Construction – Lessons

U.S. Army
Corps of
Engineers



- Include a defined number of **additional soil borings** and **core borings** as part of the construction program
- Define **required remedial actions** if $f'sc$ is low or if penetration is not achieved
- Require use of **computerized data collection and injection control** for QC


Summary – Design & Construction

U.S. Army
Corps of
Engineers



The use of soil mix shear walls to provide reinforcing of the loose soil against seismic deformations and liquefaction shear slides at the Clemson Dams was feasible and cost effective

Clemson Diversion Dams



Clemson University can continue to safely perform Football Rituals in Death Valley.