Waste Treatment Using Molten Salt Oxidation Technology

> Tim Rivers MSE Technology Applications, Inc.

15<sup>th</sup> Annual Global Demilitarization Symposium & Exhibition





#### Coauthors

 Dr. Solim Kwak, Majid Moosavi, John Wallace U.S. Army Defense Ammunition Center (DAC)

## **Program Sponsors**

- Program Sponsor:
  - United States Defense Ammunition Center
- Contract Administered by:
  - Naval Surface Warfare Center-Crane
    - Contract Number, N00164-05-C-4721

## **Technology Background**

- Molten salt oxidation (MSO) is a flameless oxidation process
- Operates at lower temperature than incineration
  - Approximately 800<sup>0</sup>C
- Eutectic salt mixture captures acid gas elements
  - Na<sub>2</sub>CO<sub>3</sub> and K<sub>2</sub>CO<sub>3</sub> mixture

## **Process Chemistry**

- Described at previous Global Demilitarization Symposiums
- Contaminants of concern
  - Simple organics (explosive, contaminated carbon)
    - $2C_aH_b + (2a + b/2)O_2 \rightarrow 2aCO_2 + bH_2O$
  - Nitrogen-bearing organic wastes
    - $C_aH_bN_c + O_2 \rightarrow CO_2 + H_2O + N_2 + NO_x$

## Project Background

- MSE was tasked to design and deliver prototype MSO system for energetic contaminated material and other waste streams at DEFAC facility in South Korea
- Optimized prototype system uses background information developed from pilot-scale system runs at DAC and BGAD
  - Pilot scale operation described in previous Demil Symposiums

## Process Design Basis

- Designed to treat secondary wastes resulting from operations at DEFAC facility in Korea
  - Explosive, contaminated, activated carbon
  - Water treatment plant deionization resins
  - Synthetic oils
  - Approximately 2.5 times larger feedrate than pilot-scale system
    - Feedrate of 240 to 250 ml/min

# Large Scale Prototype System



## Feed Preparation System

- Continuous batch feed preparation system
- Designed to grind feedstock to less than 100 mesh
- Sweco high energy mill
- Sweco vibratory screen
- Progressive cavity pumps to recirculate feedstock
- Explosion proof motors and controls



## Grinding Mill Details

- Sweco Model 38L
- 2.5 Hp grinding motor
- Fiberglass lined grinding tub
- Ceramic cylindrical grinding media



## Screen Separator Details

- Sweco ZS30 vibro energy separator
- 0.5 Hp motor
- 100 mesh separator screen
- PVC screen cleaning cylinders





# Reactor System General Arrangement




# **Reactor Description**



#### **Reactor Illustration**

- 18 inch diameter reactor
- 120 inches high
- •Single diameter throughout entire reactor length
- 19 resistance heaters
- Alloy 600 reactor body

•Downcomer assembly injects feedstock into bottom of salt mixture



## **Reactor Heating Elements**

- 19 radiant heating elements
- Elements rated for 5000 watts per element
- Normal resistance of element is approximately 9 ohms
- Reactor operates in excess of 800°C



#### Reactor Side Heating Element

- Side elements rated for continuous operation at 1500°C
- Elements approximately 1.5 inches from reactor vessel



## Feed Injection System

- Dual Peristaltic Pumps regulate flow of feed into reactor.
- One pump is in standby while one operated



## **Reactor Top**

- Provides penetrations for reactor
  - Relief port
  - Offgas port
  - Salt removal port
  - Temperature measurement port
  - Downcomer port



## Offgas System

- Offgas cooler
- Cools gas from approximately 750°C to 210°C
- Quick cooling of gas promotes salt recondensation in salt trap
- Process lines heat traced to decrease heat-up time and keep offgas above dew point



## Salt Trap

 Salt trap is designed to capture cooled salt particulate





- Baghouse
  - Automatic cleaning system
  - Insulated and heat-traced
- Bags are constructed of a combination of Teflon and fiberglass
  - Rated for 215<sup>dc</sup>C continuous duty
  - Nine, 60 inch bags





- High Efficency Particulate Filter
  - HEPA filter
  - Insulated
  - HEPA filter designed for 260°C continuous duty
  - Designed for 99.97% removal efficiency of particulate less than 0.3 micron





- Induced Draft Blower
  - Maintains system at negative pressure
  - Nominally maintained at –3 inches water column in reactor
  - 316 stainless steel internals



#### NOx reduction System

- Offgas is reheated to above 300°C in 30 kW reheater
- CO catalyst treats carbon monoxide
- Anhydrous ammonia is injected into system
- NOx catalyst reacts with ammonia and forms nitrogen and water



## **Catalyst Internals**

- CO catalysts are constructed of platinum doped ceramic
- NOX catalysts are constructed of titanium dioxide doped ceramic
- 400°C maximum operating temperature



- Continuous Emissions Monitor
  - Heated probe
  - Automatic calibration
  - Multi analyzer
    - CO, CO2, O2, NO, NO2, SO2, THC, Ammonia



## Salt Evacuation System

- Draws a deep vacuum on storage vessel to remove salt from MSO reactor
- Remotely controlled from control room




## **Operation Summary**

- Three demonstration test series have been run to define process parameters
- System ran approximately 120% of design basis using simulated feedstocks
- Approximately 150 hours of accumulated operation on the reactor and offgas system
- Starting 300 hour reliability and maintainability test series

## **Demonstration Test Summary**

- Carbon Monoxide concentrations remained well below emission limits throughout test
- Reactor pressure maintained below atmospheric majority of test



## **Continuously Monitored Emissions**

Regulated Constituent	ROK Regulated Limit	Typical Operating Values
NOx	120 ppm *	20 – 30 ppm*
SOx	70 ppm*	5 – 15 ppm*
СО	200 ppm*	20 – 100 ppm*
Ammonia	100 ppm	5 – 25 ppm

### Start-up Issues

- Salt carryover from reactor
- Salt is volatilized in reactor and re-condenses in offgas piping upstream of gas cooler





## Start-up Issues

- Heater Failures
- Resistance heaters prematurely failed during start-up testing
- Larger diameter reactor requires higher duty cycle of heaters
- New heaters installed with higher duty cycle and temperature rating



## **DEFAC MSO Project Status**

- Performing system RAM tasks through July
- Training DAC staff to operate the system
- Scheduling for installation in the DEFAC facility in FY08



