

National Defense Industrial Association

6th Annual Disruptive Technologies Conference


“SCIF Construction: Unraveling The Mystery”

Jason Phillippe, Director
Intelligence Programs and Operations
Copper River Information Technology

Joseph Cooper, President
SCIF Constructors, LLC

“SCIF Construction: Unraveling The Mystery”

▶ History of ICD 705

- National Intelligence Strategy “Uniformity and Reciprocity”
 - Formation and involvement of the Physical and Technical Security Working Group (PTSEWG)
 - New policy structure (ICD’s, ICPG’s, ICPM’s and ICS)
 - Changes and challenges of ICD 705
- 

“SCIF Construction: Unraveling The Mystery”

- ▶ Significant Policy changes from DCID 6/9 to ICD 705
 - Additional new labor categories (Site Security Manager, Construction Security Technician, Admin Support)
 - Emergency Plans and Required SCIF Document Storage
 - Defined “Security in Depth”
 - No more “SCIF within a SCIF” with “Compartmented Areas”etc.....

“SCIF Construction: Unraveling The Mystery”

▶ Significant Construction Change Requirements

- Specifies precisely how to build a SCIF wall
 - *Includes* detailed diagrams
- 16 gauge steel studs 16 inches on center
- $\frac{3}{4}$ inch pressure treated plywood on “enhanced walls”
- Allows use of SCIF Clips vs welding for 9 gauge install

“SCIF Construction: Unraveling The Mystery”

- ▶ The new paradigm for SCIF construction and associated costs.....
 - Industry cost study by ISWG
 - Average SCIF Cost 24.2% higher
 - New clearance requirements in SCIF construction
 - SSM requires TS/SCI
 - Alarm maintenance techs require TS/SCI
 - Timeline for new policy implementation
 - Impact and implementation